



# NDC-110

## projects

Well	Start date	End date
Khesht 1	03/10/2007	03/31/2007
Khesht C	04/10/2007	08/02/2007
Khesht A	08/12/2007	10/19/2007
Khesht B	10/27/2007	01/10/2008
Khesht 5	01/26/2008	04/19/2008
Serkan 5	05/14/2008	09/26/2008
Paydar Gharb 12	10/16/2008	03/13/2009
Paydar Gharb 13	04/19/2009	08/08/2010
Paydar Gharb 15	09/17/2010	09/06/2011
Paydar Gharb 17	09/18/2011	06/02/2012
Dehloran Gharb 28	06/24/2012	06/08/2013
Dehloran 30	08/09/2013	04/13/2014
Paydar Gharb 26	04/27/2014	10/15/2014
Paydar Gharb 27	11/03/2014	09/17/2014
Paydar Gharb 29	10/05/2015	01/29/2016
Aban 11	03/05/2016	06/27/2016
Cheshmeh Khosh 22	07/09/2016	01/12/2017
Cheshmeh Khosh 11	02/08/2017	06/21/2017
Paydar Gharb 33	07/04/2017	09/17/2017
Paydar Gharb 34	10/01/2017	04/08/2018
Cheshmeh Khosh 10	04/25/2018	06/09/2018
Dehloran 26	10/03/2018	10/22/2018

## Specification

Power	4no. CAT 3516
Max Depth Drilled	7000 m
Max Hook Load	1000000 Lb
Max Drill String Weight	450 Ton
Drawworks Power	2000 HP
Drilling Line Diameter	1 ½"
Mud Pumps	3No. F-1600
Top Drive	TDS-11SA
Well Control	Shaffer Type 13 5/8" BOP 5K
Choke Monifold	5000 Psi
Standpipe Pressure	5000 Psi
Active Mud System	2400 Bbl