



NDC-111

Projects

Well	Start Date	End date
Sarajeh 12	04/07/2008	07/05/2008
Khangiran 55	07/25/2008	11/09/2008
Khangiran 56	11/20/2008	04/12/2009
Khangiran 57	04/23/2009	06/25/2010
Khangiran 59	07/24/2010	01/22/2011
Khangiran 62	02/02/2011	08/30/2011
Khangiran 64	09/08/2011	03/15/2012
Khangiran 67	03/26/2012	09/03/2012
Khangiran 69	09/13/2012	03/13/2013
Khangiran 70	03/22/2013	12/04/2013
Cheshmeh Khush 20	01/06/2014	06/01/2014
Paydar Gharb 21	06/19/2014	02/18/2015
Paydar Gharb 20	04/04/2015	06/17/2015
South Azadegan 103	02/11/2016	12/22/2016
South Azadegan 129	02/14/2017	10/12/2017
South Azadegan 123	11/17/2017	04/27/2018
South Azadegan 103	05/24/2018	06/25/2018
South Azadegan 129	06/07/2018	10/22/2018
South Azadegan 113	11/10/2018	7/14/2019

Specification

Power	4no. CAT 3516
Max Depth Drilled	7000 m
Max Hook Load	1000000 Lb
Max Drill String Weight	450 Ton
Drawworks Power	2000 HP
Drilling Line Diameter	1 ½"
Mud Pumps	3No. F-1600
Top Drive	TDS-11SA
Well Control	Shaffer Type 13 5/8" BOP 5K
Choke Monifold	5000 Psi
Standpipe Pressure	5000 Psi
Active Mud System	2400 Bbl