



NDC-113

Projects

Well	Start Date	End Date
Sarajeh 13	08/25/2008	01/01/2009
Sarajeh 14	01/15/2009	06/08/2009
Sarajeh 12	07/06/2009	08/14/2009
Sarajeh 13	08/28/2009	09/29/2009
Sarajeh 10	10/08/2009	11/17/2009
Gonbadli 10	01/16/2010	10/18/2010
Khangiran 41	11/05/2010	12/08/2010
Khangiran 60	12/18/2010	08/09/2011
Khangiran 63	08/20/2011	01/10/2012
Khangiran 66	02/20/2012	09/16/2012
Gonbadli 11	09/27/2012	06/13/2013
Khangiran 71	06/25/2013	02/16/2014
Khangiran 72	02/26/2014	07/17/2014
Khangiran 73	08/17/2014	03/22/2015
Khangiran 74	06/30/2015	02/04/2016

Khangiran 49	02/21/2016	06/13/2016
Khangiran 64	06/25/2016	11/26/2016
Gonbadli 12	12/07/2016	03/02/2016
Khangiran 75	03/16/2017	09/07/2017
Khangiran 38	09/22/2017	11/17/2017
Khangiran 77	12/31/2017	05/20/2018
Khangiran 76	06/23/2018	10/21/2018
Khangiran 42	12/24/2018	01/31/2019
Khangiran 43	02/25/2019	07/07/2019
Khangiran 21	07/23/2019	08/30/2019
Khangiran 8	09/07/2019	12/22/2019
Khangiran 77	04/26/2020	06/30/2020
Khangiran 71	07/15/2020	09/25/2020
Khangiran 78	02/21/2021	

Specifcaton

Power	4no. CAT 3512B
Max Depth Drilled	7000 m
Max Hook Load	1000000 Lb
Max Drill String Weight	450 Ton
Drawworks Power	2000 HP
Drilling Line Diameter	1 ½"
Mud Pumps	3No. F-1600
Top Drive	TDS-115A
Well Control	Shaffer Type 13 5/8" BOP 5K
Choke Monifold	5000 Psi
Standpipe Pressure	5000 Psi
Active Mud System	2400 Bbl