



NDC-117

Projects

Well	Start Date	End Date
Hendijan 6	06/05/2009	07/29/2009
Hendijan 10	08/13/2009	06/02/2010
Mahshahr 1	07/01/2010	01/05/2012
Hendijan 10	01/23/2012	04/29/2012
Doroud 43	06/26/2012	10/02/2012
Khark 47	10/21/2012	03/21/2013
Khark 34	03/29/2013	09/25/2013
South Azadegan 113	05/18/2016	10/27/2017
Ahwaz 510	03/14/2018	07/03/2018
Ahwaz 512	07/19/2018	08/18/2018
Maroun 471	01/27/2019	09/23/2019
Ahwaz 519	10/18/2019	03/24/2020
Maroun 82	05/30/2021	07/31/2021
Maroun 479	08/31/2021	

Specification

Power	4no. CAT 3512B
Max Depth Drilled	7000 m
Max Hook Load	1000000 Lb
Max Drill String Weight	450 Ton
Drawworks Power	2000 HP
Drilling Line Diameter	1 ½"
Mud Pumps	3No. FL-1600
Top Drive	TDS-11SA
Well Control	Cameron 13 5/8" 10K
Choke Monifold	10000 Psi
Standpipe Pressure	5000 Psi
Active Mud System	2400 Bbl