



# NDC-112

## Projects

Well	Start Date	End Date
Sarkhun 15	04/22/2008	10/27/2008
Sarkhun 16	11/16/2008	03/14/2009
Aban 2	05/11/2009	09/25/2009
Paydar Gahr b 4	10/16/2009	05/21/2010
Naft Shahr 24	06/28/2010	07/12/2010
Sumar 1	07/27/2010	08/14/2010
Aban 3	09/06/2010	05/03/2011
Aban 2	05/12/2011	11/16/2011
Aban 4	11/25/2011	05/23/2012
Danan 8	06/28/2012	03/17/2013
Danan 9	03/28/2013	09/08/2013
Dehloran 31	09/26/2013	05/21/2014
Aban 08	06/05/2014	03/13/2015
Aban 009	03/23/2015	10/11/2015
Paydar Gharb 31	10/25/2015	02/14/2016
Dehloran 35	03/25/2016	10/30/2016
Paydar Gharb 12	12/13/2016	01/09/2017
Paydar Gharb 19	01/19/2017	04/01/2017
Cheshmeh Khosh 018	05/09/2017	08/28/2017
Aban 12	09/11/2017	11/08/2017
Dehloran 37	12/08/2017	06/11/2018
Dehloran 38	07/04/2018	11/11/2018
Dehloran 40	12/06/2018	06/22/2019
Dehloran 25	07/06/2019	03/29/2020
Dehloran 43	04/20/2020	04/20/2021

## Specification

Power	4no. CAT 3512B
Max Depth Drilled	7000 m
Max Hook Load	1000000 Lb
Max Drill String Weight	450 Ton
Drawworks Power	2000 HP
Drilling Line Diameter	1 ½"
Mud Pumps	3No. F-1600
Top Drive	TDS-11SA
Well Control	Shaffer Type 13 5/8" BOP 5K
Choke Monifold	5000 Psi
Standpipe Pressure	5000 Psi
Active Mud System	2400 Bbl